ELECTRICAL DESIGN GROUP
ELECTRICAL BUILDING SERVICES CONSULTANTS
P.O. Box 15, SHERWOOD Q. 4075
Phone: (07) 3278 4375
Website: www.edg.net.au Email: brisbane@edg.net.au

C3351a - REWARD PET FOODS, WILSONTON **C3351a-0007(B).xls**

DISTRIBUTION BOARD DB-2-2 (SOUTH EXISTING)

REVISION B - 28 JANUARY 2025

	REV
UPDATE THE EXISTING SWITCHBOARD WITH THE FOLLOWING ADDITIONAL CIRCUITS / SWITCHGEAR. REMOVE ALL EXISTING SWITCHGEAR MADE REDUNDANT BY THE WORKS. IT IS ACCEPTABLE TO UTILISE SPARE SWITCHGEAR OR SWITCHGEAR MADE REDUNDANT BY THE WORKS FOR THE NEW CIRCUITS IF IT IS IN GOOD CONDITION AND HAS THE APPROPRIATE RATING AND FUNCTION. UPDATE THE SCHEDULE AT PRACTICAL COMPLETION SO THE USE AND LOCATION OF ALL CIRCUITS CAN BE SIMPLY IDENTIFIED.	A

CIRC	PH	CIRCUIT BREAKER (amps)	CONTROL EQUIPMENT	CABLE SIZE (mm^2)	LOCATION	CIRCUIT USE	
P1	1	20	RCBO	2.5	DRYERS	GPO	A
P2	1	20	RCBO	2.5	DRYERS	GPO	A
P3	1	20	RCBO	2.5	PACKING	DOORS	A
P4	1	20	RCBO	2.5	PACKING	GPO	A
P5	1	20	RCBO	2.5	PACKING	GPO	A
P6	1	20	RCBO	2.5	PACKING	GPO	A
P7	1	20	RCBO	2.5	PACKING	GPO	A
P8	1	20	RCBO	2.5	PACKING	GPO	A
P9	1	20	RCBO	2.5	PACKING	GPO	A
P10	1	20	RCBO	2.5	PACKING	GPO	A
P11	1	20	RCBO	2.5	PACKING	GPO	A
P12	1	20	RCBO	2.5	PACKING	GPO	A
P13	1	20	RCBO	2.5	PACKING	GPO	A
P14	1	20	RCBO	2.5	PACKING	GPO	A
P15	1	20	RCBO	2.5	QA	GPO	A
P16	1	20	RCBO	2.5	ENTRY	GPO	A
P17	1	20	RCBO	2.5	PACKING	BUG ZAPPER	A
P18	1	20	RCBO	2.5	PACKING	DOORS	A
P19	3	20	RCBO	2.5	INTERNAL	14.5KW HWS	B
P20	1	20	RCBO	2.5	EXTERNAL	AIRCONDITYIONING	B
L1	1	20	RCBO	2.5	PACKING	LIGHTS	A
L2	1	20	RCBO	2.5	QA	LIGHTS	A
L3	1	20	RCBO	2.5	DRYERS	LIGHTS	A

ELECTRICAL DESIGN GROUP BRISBANE PTY LTD ACN 092 710 793
TRADING AS – ELECTRICAL DESIGN GROUP ABN 96 092 710 793