



ELECTRICAL DESIGN GROUP

ELECTRICAL BUILDING SERVICES CONSULTANTS

P.O. Box 15, SHERWOOD Q. 4075

Phone: (07) 3278 4375

Website: www.edg.net.au Email: brisbane@edg.net.au

C3770a - FEDERAL HOTEL, TOOWOOMBA

C3770a-0001(B).xls


ELECTRICAL SERVICES CONTRACT DOCUMENT SCHEDULE

REVISION B - 28 AUGUST 2026

ISSUING INFORMATION				DATE OF ISSUE							
	DAY	14	28								
	MONTH	08	08								
	YEAR	26	26								
	REASON FOR ISSUE	T	T								
A = APPROVAL C = CONSTRUCTION N = COORDINATION P = PRELIMINARY T = TENDER											

DISTRIBUTION				NUMBER OF COPIES							
WWW.EDG.NET.AU				1E	1E						
BSPN ARCHITECTURE				1E	1E						
P = PRINT T = TRACING D = DISC E = EMAIL F = FAX											

DOCUMENTS				REVISION							
C3770a-E01.dwg	LEGEND & DETAILS	A									
C3770a-E02.dwg	NOTES	A									
C3770a-E03.dwg	FLOOR PLAN	A	B								
C3770a-E04.dwg	REFLECTED CEILING PLAN	A									
C3770a-E05.dwg	JOINERY & WALL LIGHTING PLAN	A									
C3770a-0001.xls	CONTRACT DOCUMENT SCHEDULE	A	B								
C3770a-0002.xls	EQUIPMENT SCHEDULE	A	B								
C3770a-0004.xls	LIGHTING CONTROL SCHEDULE	A									
C3770a-0005.xls	DISTRIBUTION BOARD DB-1B SCHEDULE	A									
C3770a-0006.xls	DISTRIBUTION BOARD DB-4 SCHEDULE	A									
C3770a-0001.zip	FITTING & OUTLET DATASHEETS	A									



ELECTRICAL DESIGN GROUP

ELECTRICAL BUILDING SERVICES CONSULTANTS

P.O. Box 15, SHERWOOD Q. 4075

Phone: (07) 3278 4375 Fax: (07) 3716 0222

Web Site: www.edg.net.au Email: brisbane@edg.net.au

C3770a - FEDERAL HOTEL, TOOWOOMBA

C3770a-0002(B).xls

ELECTRICAL EQUIPMENT SCHEDULE


REVISION B - 28 AUGUST 2026

THE LIGHT FITTING SUPPLIER CONTACT DETAILS MAY BE AVAILABLE ON THE EDG WEBSITE VIA THE FOLLOWING LINK
www.edg.net.au/Links/Lighting.htm

TYPE	LAMPS	DESCRIPTION	COLOUR / ACCESSORY	CATALOGUE No	REV
L1	14.4W/M 2700K LED	LED STRIP WITHIN A SCREW FIXED EXTRUSION C/W DIFFUSER WITHIN THE SUSPENDED BAR FEATURE BULKHEAD AS PER THE ARCHITECTURAL DETAIL. ENSURE ALL CABLING IS CONCEALED. PROVIDE THE STRIP WITH REMOTE DALI DIMMABLE POWER SUPPLIES AS REQUIRED LOCATE THE POWER SUPPLIES IN A CONCEALED ACCESSIBLE POSITION NOTED ON THE AS CONSTRUCTED DOCUMENTS.	NATURAL	RAPID LED R2334 2700 K PLUS ALUMINIUM EXTRUSION OPAL DIFFUSER AND POWER SUPPLY & DALI CONTROLLER	A
L2	10W/M 2700K LED	IP67 LED FLEX SCREW FIXED WITHIN THE SUSPENDED BAR FEATURE BULKHEAD AS PER THE ARCHITECTURAL DETAIL. ENSURE ALL CABLING IS CONCEALED. PROVIDE THE STRIP WITH REMOTE DALI DIMMABLE POWER SUPPLIES AS REQUIRED LOCATE THE POWER SUPPLIES IN A CONCEALED ACCESSIBLE POSITION NOTED ON THE AS CONSTRUCTED DOCUMENTS. CONFIRM THE BEND PLANE (TOP OR SIDE) ON SITE WITH THE ARCHITECT.	NATURAL	RAPID LED R2321 OR R2332 2700 K PLUS ALUMINIUM EXTRUSION OPAL DIFFUSER AND POWER SUPPLY & DALI CONTROLLER	B
L3	14.4W/M 2700K LED	LED STRIP WITHIN A SCREW FIXED EXTRUSION C/W DIFFUSER WITHIN CURTAIN PELMET AS PER THE ARCHITECTURAL DETAIL. PROVIDE THE STRIP WITH REMOTE DALI DIMMABLE POWER SUPPLIES AS REQUIRED LOCATE THE POWER SUPPLIES IN A CONCEALED ACCESSIBLE POSITION NOTED ON THE AS CONSTRUCTED DOCUMENTS.	NATURAL	RAPID LED R2334 PLUS ALUMINIUM EXTRUSION AND POWER SUPPLY & DALI CONTROLLER	A
L4	10W/M 2700K LED	IP67 LED FLEX SCREW FIXED WITHIN THE GAMING CEILING FEATURE AS PER THE ARCHITECTURAL DETAIL. PROVIDE THE STRIP WITH REMOTE DALI DIMMABLE POWER SUPPLIES AS REQUIRED LOCATE THE POWER SUPPLIES IN A CONCEALED ACCESSIBLE POSITION NOTED ON THE AS CONSTRUCTED DOCUMENTS. CONFIRM THE BEND PLANE (TOP OR SIDE) ON SITE WITH THE ARCHITECT.	NATURAL	RAPID LED R2321 OR R2332 2700 K PLUS ALUMINIUM EXTRUSION OPAL DIFFUSER AND POWER SUPPLY & DALI CONTROLLER	B
L5	14.4W/M 2700K LED	LED STRIP WITHIN A SCREW FIXED EXTRUSION C/W DIFFUSER WITHIN THE REAR BAR JOINERY AS PER THE ARCHITECTURAL DETAIL. ENSURE ALL CABLING IS CONCEALED. PROVIDE THE STRIP WITH REMOTE DALI DIMMABLE POWER SUPPLIES AS REQUIRED LOCATE THE POWER SUPPLIES IN A CONCEALED ACCESSIBLE POSITION NOTED ON THE AS CONSTRUCTED DOCUMENTS.	NATURAL	RAPID LED R2334 2700 K PLUS ALUMINIUM EXTRUSION OPAL DIFFUSER AND POWER SUPPLY & DALI CONTROLLER	A
L6	15W 3000K LED	90 DIA RECESSED DOWNLIGHT C/W 24 DEG BEAM REMOTE DALI DIMMABLE DRIVER	WHITE	RAPID R1078-WH-15W-WW-DALI	A
L7	15W 3000K LED	90 DIA RECESSED DOWNLIGHT C/W 24 DEG BEAM REMOTE DALI DIMMABLE DRIVER	BLACK	RAPID R1078-WH-15W-WW-DALI	A
L8	15W 3000K LED	90 DIA RECESSED DOWNLIGHT C/W 24 DEG BEAM REMOTE DALI DIMMABLE DRIVER	WHITE	RAPID R1078-WH-15W-WW-DALI	A
L9	15W 3000K LED	75 DIA RECESSED ADJUSTABLE DOWNLIGHT C/W REMOTE DALI DIMMABLE DRIVER	BLACK	RAPID R1074-WH-15W-WW-DALI	B

C3770a-0002(B).xls

Pages inc. any attach. 1 of 7



ELECTRICAL DESIGN GROUP

ELECTRICAL BUILDING SERVICES CONSULTANTS

P.O. Box 15, SHERWOOD Q. 4075

Phone: (07) 3278 4375 Fax: (07) 3716 0222

Web Site: www.edg.net.au Email: brisbane@edg.net.au

C3770a - FEDERAL HOTEL, TOOWOOMBA


C3770a-0002(B).xls

ELECTRICAL EQUIPMENT SCHEDULE

REVISION B - 28 AUGUST 2026

THE LIGHT FITTING SUPPLIER CONTACT DETAILS MAY BE AVAILABLE ON THE EDG WEBSITE VIA THE FOLLOWING LINK
www.edg.net.au/Links/Lighting.htm

TYPE	LAMPS	DESCRIPTION	COLOUR / ACCESSORY	CATALOGUE No	REV
L10	30W 4000K LED	1200 x 300 LAY IN FLAT PLATE LED FITTING C/W REMOTE DRIVER MOUNTED IN A FLUSH RECESSED PB MOUNTING KIT	WHITE TRIM	RAPID LED R3206	A
S1	10W/M 2700K LED	IP67 LED FLEX SCREW FIXED BEHIND THE WALL FEATURE IN A FULL CIRCLE AS PER THE ELEVATION AND ARCHITECTURAL DETAIL. PROVIDE THE STRIP WITH REMOTE POWER SUPPLY LOCATED IN A CONCEALED ACCESSIBLE POSITION NOTED ON THE AS CONSTRUCTED DOCUMENTS. CONFIRM THE BEND PLANE (TOP OR SIDE) ON SITE WITH THE ARCHITECT.	WHITE	RAPID LED R2321 OR R2322 - 2700K + POWER SUPPLY & DALI CONTROLLER	A
S2	14.4W/M 2700K LED	LED STRIP WITHIN A SCREW FIXED EXTRUSION C/W DIFFUSER WITHIN PELMET UNDER THE FRONT FACE OF THE SEAT AS PER THE ARCHITECTURAL DETAIL. PROVIDE THE STRIP WITH REMOTE DALI DIMMABLE POWER SUPPLIES AS REQUIRED LOCATE THE POWER SUPPLIES IN A CONCEALED ACCESSIBLE POSITION NOTED ON THE AS CONSTRUCTED DOCUMENTS.	NATURAL	RAPID LED R2334 2700 K PLUS ALUMINIUM EXTRUSION OPAL DIFFUSER AND POWER SUPPLY & DALI CONTROLLER	A
S3	14.4W/M 2700K LED	TWIN RUNS OF LED STRIP WITHIN A SCREW FIXED EXTRUSION C/W DIFFUSER RECESSED INTO THE JOINERY AS PER THE ELEVATION AND THE ARCHITECTURAL DETAIL. PROVIDE THE STRIP WITH REMOTE DALI DIMMABLE POWER SUPPLIES AS REQUIRED LOCATE THE POWER SUPPLIES IN A CONCEALED ACCESSIBLE POSITION NOTED ON THE AS CONSTRUCTED DOCUMENTS.	NATURAL	RAPID LED R2334 2700 K PLUS ALUMINIUM EXTRUSION OPAL DIFFUSER AND POWER SUPPLY & DALI CONTROLLER	A
S4	10W/M 2700K LED	IP67 LED FLEX SCREW FIXED RECESSED ONTO THE BAR FRONT AS PER THE ARCHITECTURAL DETAIL. PROVIDE THE STRIP WITH REMOTE DALI DIMMABLE POWER SUPPLIES AS REQUIRED LOCATE THE POWER SUPPLIES IN A CONCEALED ACCESSIBLE POSITION NOTED ON THE AS CONSTRUCTED DOCUMENTS. CONFIRM THE BEND PLANE (TOP OR SIDE) ON SITE WITH THE ARCHITECT.	NATURAL	RAPID LED R2321 OR R2322 - 2700K + POWER SUPPLY & DALI CONTROLLER	B
S5	14.4W/M 2700K LED	MULTIPLE RUNS OF LED STRIP WITHIN A SCREW FIXED EXTRUSION C/W DIFFUSER RECESSED INTO THE REAR BAR JOINERY AS PER THE ELEVATION AND THE ARCHITECTURAL DETAIL. PROVIDE THE STRIP WITH REMOTE DALI DIMMABLE POWER SUPPLIES AS REQUIRED LOCATE THE POWER SUPPLIES IN A CONCEALED ACCESSIBLE POSITION NOTED ON THE AS CONSTRUCTED DOCUMENTS.	NATURAL	RAPID LED R2334 2700 K PLUS ALUMINIUM EXTRUSION OPAL DIFFUSER AND POWER SUPPLY & DALI CONTROLLER	A



ELECTRICAL DESIGN GROUP

ELECTRICAL BUILDING SERVICES CONSULTANTS

P.O. Box 15, SHERWOOD Q. 4075

Phone: (07) 3278 4375 Fax: (07) 3716 0222

Web Site: www.edg.net.au Email: brisbane@edg.net.au

C3770a - FEDERAL HOTEL, TOOWOOMBA


C3770a-0002(B).xls

ELECTRICAL EQUIPMENT SCHEDULE

REVISION B - 28 AUGUST 2026

THE LIGHT FITTING SUPPLIER CONTACT DETAILS MAY BE AVAILABLE ON THE EDG WEBSITE VIA THE FOLLOWING LINK
www.edg.net.au/Links/Lighting.htm

TYPE	LAMPS	DESCRIPTION	COLOUR / ACCESSORY	CATALOGUE No	REV
S6	10W/M 2700K LED	IP67 LED FLEX SCREW FIXED RECESSED ONTO THE BAR FRONT AS PER THE ARCHITECTURAL DETAIL. PROVIDE THE STRIP WITH REMOTE DALI DIMMABLE POWER SUPPLIES AS REQUIRED LOCATE THE POWER SUPPLIES IN A CONCEALED ACCESSIBLE POSITION NOTED ON THE AS CONSTRUCTED DOCUMENTS. CONFIRM THE BEND PLANE (TOP OR SIDE) ON SITE WITH THE ARCHITECT.	WHITE	RAPID LED R2321 OR R2322 - 2700K + POWER SUPPLY & DALI CONTROLLER	A
S7	14.4W/M 2700K LED	MULTIPLE RUNS OF LED STRIP WITHIN A SCREW FIXED EXTRUSION C/W DIFFUSER RECESSED INTO THE REAR BAR JOINERY AS PER THE ELEVATION AND THE ARCHITECTURAL DETAIL. PROVIDE THE STRIP WITH REMOTE DALI DIMMABLE POWER SUPPLIES AS REQUIRED LOCATE THE POWER SUPPLIES IN A CONCEALED ACCESSIBLE POSITION NOTED ON THE AS CONSTRUCTED DOCUMENTS.	NATURAL	RAPID LED R2334 2700 K PLUS ALUMINIUM EXTRUSION OPAL DIFFUSER AND POWER SUPPLY & DALI CONTROLLER	A
S8	10W/M 2700K LED	IP67 LED FLEX SCREW FIXED RECESSED INTO THE REAR BAR JOINERY AS PER THE ELEVATION AND THE ARCHITECTURAL DETAIL. PROVIDE THE STRIP WITH REMOTE POWER SUPPLY LOCATED IN A CONCEALED ACCESSIBLE POSITION NOTED ON THE AS CONSTRUCTED DOCUMENTS. CONFIRM THE BEND PLANE (TOP OR SIDE) ON SITE WITH THE ARCHITECT.	WHITE	RAPID LED R2321 OR R2322 - 2700K + POWER SUPPLY & DALI CONTROLLER	A
S9	14.4W/M 2700K LED	MULTIPLE RUNS OF LED STRIP WITHIN A SCREW FIXED EXTRUSION C/W DIFFUSER RECESSED INTO THE JOINERY AS PER THE ELEVATION AND THE ARCHITECTURAL DETAIL. PROVIDE THE STRIP WITH REMOTE DALI DIMMABLE POWER SUPPLIES AS REQUIRED LOCATE THE POWER SUPPLIES IN A CONCEALED ACCESSIBLE POSITION NOTED ON THE AS CONSTRUCTED DOCUMENTS.	NATURAL	RAPID LED R2334 2700 K PLUS ALUMINIUM EXTRUSION OPAL DIFFUSER AND POWER SUPPLY & DALI CONTROLLER	A
S10	14.4W/M 2700K LED	MULTIPLE RUNS OF LED STRIP WITHIN A SCREW FIXED EXTRUSION C/W DIFFUSER RECESSED INTO THE JOINERY AS PER THE ELEVATION AND THE ARCHITECTURAL DETAIL. PROVIDE THE STRIP WITH REMOTE DALI DIMMABLE POWER SUPPLIES AS REQUIRED LOCATE THE POWER SUPPLIES IN A CONCEALED ACCESSIBLE POSITION NOTED ON THE AS CONSTRUCTED DOCUMENTS.	NATURAL	RAPID LED R2334 2700 K PLUS ALUMINIUM EXTRUSION OPAL DIFFUSER AND POWER SUPPLY & DALI CONTROLLER	A
S11	10W/M 2700K LED	IP67 LED FLEX SCREW FIXED RECESSED ONTO THE UNDERSIDE OF THE COUNTER AS PER THE ARCHITECTURAL DETAIL. PROVIDE THE STRIP WITH REMOTE DALI DIMMABLE POWER SUPPLIES AS REQUIRED LOCATE THE POWER SUPPLIES IN A CONCEALED ACCESSIBLE POSITION NOTED ON THE AS CONSTRUCTED DOCUMENTS. CONFIRM THE BEND PLANE (TOP OR SIDE) ON SITE WITH THE ARCHITECT.	WHITE	RAPID LED R2321 OR R2322 - 2700K + POWER SUPPLY & DALI CONTROLLER	A



ELECTRICAL DESIGN GROUP

ELECTRICAL BUILDING SERVICES CONSULTANTS

P.O. Box 15, SHERWOOD Q. 4075

Phone: (07) 3278 4375 Fax: (07) 3716 0222

Web Site: www.edg.net.au Email: brisbane@edg.net.au

C3770a - FEDERAL HOTEL, TOOWOOMBA


C3770a-0002(B).xls

ELECTRICAL EQUIPMENT SCHEDULE

REVISION B - 28 AUGUST 2026

THE LIGHT FITTING SUPPLIER CONTACT DETAILS MAY BE AVAILABLE ON THE EDG WEBSITE VIA THE FOLLOWING LINK
www.edg.net.au/Links/Lighting.htm

TYPE	LAMPS	DESCRIPTION	COLOUR / ACCESSORY	CATALOGUE No	REV
P1	6W TRAILING EDGE DIMMABLE A60 240 VOLT E27 2200K LED LAMP	DECORATIVE 440 DIA PENDANT. CONFIRM THE SUSPENSION HEIGHT ON SITE WITH THE ARCHITECT	BRASS	ZEST LIGHTING HARA BRASS WIDE HAT PENDANT	A
P2	6W TRAILING EDGE DIMMABLE A60 240 VOLT E27 2200K LED LAMP	DECORATIVE 200DIA PENDANT. CONFIRM THE SUSPENSION HEIGHT ON SITE WITH THE ARCHITECT	GOLD	ZEST LIGHTING PIPER BELL GOLD PENDANT	A
P3	3000K 3W TRAILING EDGE DIMMABLE 240V G9 LED LAMP	DECORATIVE 130 DIA PENDANT. CONFIRM THE SUSPENSION HEIGHT ON SITE WITH THE ARCHITECT	APRICOT BRASS METAL	LIGHTING COLLECTIVE MELLOW BUD TRANSLUCENT	A
P4	6W TRAILING EDGE DIMMABLE A60 240 VOLT E27 2200K LED LAMP	DECORATIVE 200 DIA PENDANT. CONFIRM THE SUSPENSION HEIGHT ON SITE WITH THE ARCHITECT	NA	LIGHTING COLLECTIVE SMALL TRADITIONAL CERAMIC PENDANT	A
P5	INTEGRAL 3000K 7W TE DIMMABLE LED	PROVIDE EACH P5 AS FOUR SEPARATE DECORATIVE 50 DIA PENDANTS. CONFIRM THE SUSPENSION HEIGHT OF EACH PENANT ON SITE WITH THE ARCHITECT	ALABASTA	4 X NOOK COLLECTION ZEUS DUO PENDANT LIGHT	A
P6	3000K 3W TRAILING EDGE DIMMABLE 240V GU10 LED LAMP	DECORATIVE 240 DIA PENDANT. CONFIRM THE SUSPENSION HEIGHT ON SITE WITH THE ARCHITECT	NA	ZEST LIGHTING MARTINI SMOKE GLASS MINIMALIST PENDANT	A
P7	6W TRAILING EDGE DIMMABLE A60 240 VOLT E27 2200K LED LAMP	DECORATIVE 200DIA PENDANT. CONFIRM THE SUSPENSION HEIGHT ON SITE WITH THE ARCHITECT	BRONZE	ZEST LIGHTING PIPER BELL BRONZE PENDANT	A
WL01	6W TRAILING EDGE DIMMABLE A60 240 VOLT E27 2200K LED LAMP	DECORATIVE WALL LIGHT MOUNTED AS PER THE ARCHITECTURAL DETAILS	SAND	LIGHTING COLLECTIVE CONCRETE BOWL WALL SCONCE	A
WL02	4 X 3000K 5W TRAILING EDGE DIMMABLE 240V GU10 LED LAMPS	REPLACE THE EXISTING WALL LIGHTS / PROVIDE NEW AS REQUIRED	LUZ SOLID BRASS	HAVIT HV10592T	A
WL03	6W TRAILING EDGE DIMMABLE A60 240 VOLT E27 2200K LED LAMP	DECORATIVE WALL LIGHT MOUNTED AS PER THE ARCHITECTURAL DETAILS	COCOA	LIGHTING COLLECTIVE CONCRETE BOWL WALL SCONCE	A
WL04	2700K INTEGRAL TE DIMMABLE 4W LED	DECORATIVE 180 DIA WALL LIGHT MOUNTED AS PER THE ARCHITECTURAL DETAILS	FROSTED	NOOK COLLECTIONS DOME AIR WALL LIGHT	A



ELECTRICAL DESIGN GROUP

ELECTRICAL BUILDING SERVICES CONSULTANTS

P.O. Box 15, SHERWOOD Q. 4075

Phone: (07) 3278 4375 Fax: (07) 3716 0222

Web Site: www.edg.net.au Email: brisbane@edg.net.au

C3770a - FEDERAL HOTEL, TOOWOOMBA


C3770a-0002(B).xls

ELECTRICAL EQUIPMENT SCHEDULE

REVISION B - 28 AUGUST 2026

THE LIGHT FITTING SUPPLIER CONTACT DETAILS MAY BE AVAILABLE ON THE EDG WEBSITE VIA THE FOLLOWING LINK
www.edg.net.au/Links/Lighting.htm

TYPE	LAMPS	DESCRIPTION	COLOUR / ACCESSORY	CATALOGUE No	REV
WL05	3000K 5W TRAILING EDGE DIMMABLE 240V GU10 LED LAMPS	REPLACE THE EXISTING HIGH LEVEL CEILING BULKHEAD LIGHTS	BLACK	HAVIT HV1225T	A
E1	LED	EMERGENCY LIGHT: RECESSED NON-MAINTAINED EMERGENCY LIGHT. AS2293 CLASSIFICATION C0-D40 - C90-D40.	BLACK	CLEVERTRONICS CLIFE BK	A
E2	LED	EMERGENCY LIGHT: RECESSED NON-MAINTAINED EMERGENCY LIGHT. AS2293 CLASSIFICATION C0-D40 - C90-D40.	WHITE	CLEVERTRONICS CLIFE	A
EX	LED	EXIT LIGHT : MAINTAINED 24M VIEWING DISTANCE EXIT LIGHT C/W DIFFUSERS & DIRECTIONAL ARROWS AS SHOWN. CEILING OR WALL MOUNT BETWEEN 2100mm & 2700mm AFFL IF THERE IS NO VERTICAL SURFACE TO MOUNT THE FITTING ON WITHIN THIS RANGE CONFIRM THE MOUNTING HEIGHT WITH THE ENGINEER. LITHIUM ION BATTERY	WHITE	CLEVERTRONICS CSBLED	A
EX BK	LED	EXIT LIGHT : MAINTAINED 24M VIEWING DISTANCE EXIT LIGHT C/W DIFFUSERS & DIRECTIONAL ARROWS AS SHOWN. CEILING OR WALL MOUNT BETWEEN 2100mm & 2700mm AFFL IF THERE IS NO VERTICAL SURFACE TO MOUNT THE FITTING ON WITHIN THIS RANGE CONFIRM THE MOUNTING HEIGHT WITH THE ENGINEER. LITHIUM ION BATTERY	BLACK	CLEVERTRONICS CSBLED BK	A
HE1		EXISTING HEATER AND ASSOCIATED CONTROLS TO BE RETAINED. RESUPPLY THE HEATER FROM DB-4 VIA A NEW DEDICATED CIRCUIT.			A
CHANNEL x		CONTROL CHANNEL WITH A NUMERICAL REFERENCE. REFER TO THE POWER AND LIGHTING CONTROL SCHEDULE			A
LIGHTING CONTROL SWITCH PANEL 1 (SP1)		PROGRAMMABLE SWITCH PANEL C/W CENTRAL LCD DISPLAY MOUNTED AT 1000mm AFFL UNLESS NOTED OTHERWISE. BLANK OFF / REMOVE THE EXISTING ADJACENT MANUAL LIGHTING CONTROLS THAT BECOME REDUNDANT.	WHITE	ZEN CONTROL SSD	A
LIGHTING CONTROL SWITCH PANEL 2 (SP2)		PROGRAMMABLE SWITCH PANEL C/W CENTRAL LCD DISPLAY MOUNTED AT 1000mm AFFL UNLESS NOTED OTHERWISE. BLANK OFF / REMOVE THE EXISTING ADJACENT MANUAL LIGHTING CONTROLS THAT BECOME REDUNDANT.	WHITE	ZEN CONTROL SSD	A



ELECTRICAL DESIGN GROUP

ELECTRICAL BUILDING SERVICES CONSULTANTS

P.O. Box 15, SHERWOOD Q. 4075

Phone: (07) 3278 4375 Fax: (07) 3716 0222

Web Site: www.edg.net.au Email: brisbane@edg.net.au

C3770a - FEDERAL HOTEL, TOOWOOMBA

C3770a-0002(B).xls

ELECTRICAL EQUIPMENT SCHEDULE


REVISION B - 28 AUGUST 2026

THE LIGHT FITTING SUPPLIER CONTACT DETAILS MAY BE AVAILABLE ON THE EDG WEBSITE VIA THE FOLLOWING LINK
www.edg.net.au/Links/Lighting.htm

TYPE	LAMPS	DESCRIPTION	COLOUR / ACCESSORY	CATALOGUE No	REV
LIGHTING CONTROL SWITCH PANEL 3 (SP3)		PROGRAMMABLE SWITCH PANEL C/W CENTRAL LCD DISPLAY MOUNTED AT 1000mm AFFL UNLESS NOTED OTHERWISE. BLANK OFF / REMOVE THE EXISTING ADJACENT MANUAL LIGHTING CONTROLS THAT BECOME REDUNDANT.	WHITE	ZEN CONTROL SSD	A
LIGHTING CONTROL SWITCH PANEL 4 (SP4)		PROGRAMMABLE SWITCH PANEL C/W CENTRAL LCD DISPLAY MOUNTED AT 1000mm AFFL UNLESS NOTED OTHERWISE. BLANK OFF / REMOVE THE EXISTING ADJACENT MANUAL LIGHTING CONTROLS THAT BECOME REDUNDANT.	WHITE	ZEN CONTROL SSD	A
LIGHTING CONTROL SWITCH PANEL 5 (SP5)		PROGRAMMABLE SWITCH PANEL C/W CENTRAL LCD DISPLAY MOUNTED AT 1000mm AFFL UNLESS NOTED OTHERWISE. BLANK OFF / REMOVE THE EXISTING ADJACENT MANUAL LIGHTING CONTROLS THAT BECOME REDUNDANT.	BLACK	ZEN CONTROL SSD	A
LIGHTING CONTROL SWITCH PANEL 6 (SP6)		PROGRAMMABLE SWITCH PANEL C/W CENTRAL LCD DISPLAY MOUNTED AT 1000mm AFFL UNLESS NOTED OTHERWISE. BLANK OFF / REMOVE THE EXISTING ADJACENT MANUAL LIGHTING CONTROLS THAT BECOME REDUNDANT.	BLACK	ZEN CONTROL SSD	A
SINGLE POWER OUTLET		SINGLE POWER OUTLET C/W CIRCUIT IDENTIFICATION ON THE FACEPLATE BEHIND THE SURROUND MOUNT AT 300mm AFFL U.N.O. RATING 10A U.N.O.	WHITE UNLESS NOTED AS BLACK (BK)	CLIPSAL C2000 SERIES	A
DOUBLE POWER OUTLET		DOUBLE POWER OUTLET C/W CIRCUIT IDENTIFICATION ON THE FACEPLATE BEHIND THE SURROUND MOUNT AT 300mm AFFL U.N.O. RATING 10A U.N.O.	WHITE UNLESS NOTED AS BLACK (BK)	CLIPSAL C2000 SERIES	A
IP66 SINGLE POWER OUTLET		SINGLE POWER OUTLET IP6 MOUNT AT 300mm AFFL U.N.O. RATING 10A U.N.O.	GREY	CLIPSAL 56 SERIES	A
SINGLE-PHASE ISOLATOR		SINGLE-PHASE WEATHERPROOF ISOLATOR. MOUNT AT 1350mm AFFL U.N.O. RATING 20A U.N.O. CONNECT TO EQUIPMENT VIA FLEXIBLE CONDUIT.	-	CLIPSAL WHT20	A
THREE-PHASE ISOLATOR		THREE-PHASE WEATHERPROOF ISOLATOR. MOUNT AT 1350mm AFFL U.N.O. RATING 20A U.N.O. CONNECT TO EQUIPMENT VIA FLEXIBLE CONDUIT. "RSD" DENOTES ROLLER SHUTTER DOOR SUPPLY - COORDINATE LOCATION ONSITE WITH MOTOR.	-	CLIPSAL WHT35	A
LIGHT BOX CONNECTION		COORDINATE THE LOCATION AND CONNECTION OF THE POWWER SUPPLY AND DALI CONTROL WITH THE LIGHT BOX CONTRACTOR ENSURING THE CONNECTIONS ARE CONCEALED FROM VIEW.			A

C3770a-0002(B).xls

Pages inc. any attach. 6 of 7



ELECTRICAL DESIGN GROUP

ELECTRICAL BUILDING SERVICES CONSULTANTS

P.O. Box 15, SHERWOOD Q. 4075

Phone: (07) 3278 4375 Fax: (07) 3716 0222

Web Site: www.edg.net.au Email: brisbane@edg.net.au

C3770a - FEDERAL HOTEL, TOOWOOMBA


C3770a-0002(B).xls

ELECTRICAL EQUIPMENT SCHEDULE

REVISION B - 28 AUGUST 2026

THE LIGHT FITTING SUPPLIER CONTACT DETAILS MAY BE AVAILABLE ON THE EDG WEBSITE VIA THE FOLLOWING LINK
www.edg.net.au/Links/Lighting.htm

TYPE	LAMPS	DESCRIPTION	COLOUR / ACCESSORY	CATALOGUE No	REV
SIGN CONNECTION		COORDINATE THE LOCATION AND CONNECTION WITH THE SIGN CONTRACTOR ENSURING THE CONNECTION ARE PROVIDED WITH APPROPRIATE WEATHER PROTECTION AND ARE CONCEALED FROM VIEW.			A
MSB		EXISTING MAIN SWITCHBOARD TO REMAIN AND BE PROVIDED WITH A 100 AMP MCCB TO SUPPLY DB-4. MODIFY THE EXISTING MSB TO ACCOMMODATE THE NEW MCCB. THE MSB MODIFICATIONS DO NOT NEED TO COMPLY WITH A/NZS 61439.			A
MSSB		EXISTING MECHANICAL SERVICES SWITCHBOARD TO REMAIN.			A
DB-1		EXISTING KITCHEN DISTRIBUTION BOARD TO REMAIN. ALL EXISTING SWITCHGEAR THAT BECOMES REDUNDANT IS TO BE REMOVED. PROVIDE A NEW CONNECTION IN DB-1 TO SUPPLY DB-1B AS PER THE DB ELEVATION AND NOTES.			A
LC-1		EXISTING LIGHTING CONTROL SWITCHBOARD TO BE REMOVED.			A
DB-1B		REPLACE THE EXISTING LC-1 WITH A NEW DISTRIBUTION BOARD AS PER THE DB ELEVATION AND NOTES. IT IS ACCEPTABLE TO UTILISE THE EXISTING ENCLOSURE IF THE APPROPRIATE COMPONENTS AND A NEW ESCUTCHEON IS PROVIDED. DB-1B I TO MATCH THE SIZE AND COLOUR OF THE EXISTING LC-1 ENCLOSURE.			A
LC-3		EXISTING LIGHTING CONTROL SWITCHBOARD TO BE REMOVED.			A
DB-3		EXISTING OFFICE DISTRIBUTION BOARD TO REMAIN. ALL EXISTING SWITCHGEAR THAT BECOMES REDUNDANT IS TO BE REMOVED.			A
DB-R		EXISTING REFRIGERATION SWITCHBOARD TO REMAIN.			A
DB-4		NEW DISTRIBUTION BOARD DB-4 REFER TO THE NOTES AND DISTRIBUTION BOARD DB-4 SCHEDULE FOR ADDITIONAL INFORMATION AND REQUIREMENTS. PROVIDE DB-4 WITH A 4C+E 35mm SUBMAIN FROM A NEW 100A MCCB THE MSB. PROVIDE A SHOP DRAWING OF THE DB FOR APPROVAL INCLUDING ALL LIGHTING CONTROLS AS PART OF THE SHOP DRAWING.			A
DB-G		GAMING DISTRIBUTION BOARD AND ITS ASSOCIATED SUBMAIN TO BE PROVIDED BY THE GAMING ELECTRICIAN.			A



ELECTRICAL DESIGN GROUP

ELECTRICAL BUILDING SERVICES CONSULTANTS

P.O. Box 15, SHERWOOD Q. 4075

Phone: (07) 3278 4375 Fax: (07) 3716 0222

Web Site: www.edg.net.au Email: brisbane@edg.net.au


C3770a - FEDERAL HOTEL, TOOWOOMBA

C3770a-0004(A).xls

LIGHTING CONTROL SCHEDULE

REVISION A - 14 AUGUST 2026

MISCELLANEOUS EQUIPMENT				REV
ITEM		DESCRIPTION		A
SP1		WALL MOUNTED WHITE ZENCONTROL SSD MOUNTED AT 1000 AFFL CONFIGURE THE CONTROLS AS PER THE NOTES		A
SP2		WALL MOUNTED WHITE ZENCONTROL SSD MOUNTED AT 1000 AFFL CONFIGURE THE CONTROLS AS PER THE NOTES		A
SP3		WALL MOUNTED WHITE ZENCONTROL SSD MOUNTED AT 1000 AFFL CONFIGURE THE CONTROLS AS PER THE NOTES		A
SP4		WALL MOUNTED WHITE ZENCONTROL SSD MOUNTED AT 1000 AFFL CONFIGURE THE CONTROLS AS PER THE NOTES		A
SP5		WALL MOUNTED WHITE ZENCONTROL SSD MOUNTED AT 1000 AFFL CONFIGURE THE CONTROLS AS PER THE NOTES		A
SP6		WALL MOUNTED WHITE ZENCONTROL SSD MOUNTED AT 1000 AFFL CONFIGURE THE CONTROLS AS PER THE NOTES		A
CONTROL MODULE 1				A
TYPE:		ZENCONTROL ZC-CONTROLLER-PRO-3		A
DESCRIPTION		3 LINE DALI APPLICATION CONTROLLER		A
LOCATION		DIN RAIL MOUNTED WITHIN DB-4		A
CHANNEL	CONTROL	CIRCUIT		A
1	DALI DIM	DB-4 - L1 L2 AND L3		A
2	DALI DIM	DB-4 - L4 AND L5		A
3	DALI DIM	DB-4 - L6 AND L7		A
CONTROL MODULE 2				A
TYPE:		ZENCONTROL ZC-PSU		A
DESCRIPTION		DALI POWER SUPPLY		A
LOCATION		DIN RAIL MOUNTED WITHIN DB-4		A
CONTROL MODULE 3				A
TYPE:		ZENCONTROL ZC-PSU		A
DESCRIPTION		DALI POWER SUPPLY		A
LOCATION		DIN RAIL MOUNTED WITHIN DB-4		A
CONTROL MODULE 4				A
TYPE:		ZENCONTROL ZC-PSU		A
DESCRIPTION		DALI POWER SUPPLY		A
LOCATION		DIN RAIL MOUNTED WITHIN DB-4		A
CONTROL MODULE 5				A
TYPE:		LUMILINK LL-D2PH-4C-DIN		A
DESCRIPTION		4 CHANNEL DALI TRAILING EDGE PHASE DIMMER		A
LOCATION		DIN RAIL MOUNTED WITHIN DB-4		A
CHANNEL	CONTROL	CIRCUIT		A
4	TE DIM	DB-4 - L8		A
5	TE DIM			A
6	TE DIM			A
7	TE DIM			A
CONTROL MODULE 6				A



ELECTRICAL DESIGN GROUP

ELECTRICAL BUILDING SERVICES CONSULTANTS

P.O. Box 15, SHERWOOD Q. 4075

Phone: (07) 3278 4375 Fax: (07) 3716 0222

Web Site: www.edg.net.au Email: brisbane@edg.net.au


C3770a - FEDERAL HOTEL, TOOWOOMBA

C3770a-0004(A).xls

LIGHTING CONTROL SCHEDULE

REVISION A - 14 AUGUST 2026

TYPE:		LUMILINK LL-D2PH-4C-DIN			A
DESCRIPTION		4 CHANNEL DALI TRAILING EDGE PHASE DIMMER			A
LOCATION		DIN RAIL MOUNTED WITHIN DB-4			A
CHANNEL	CONTROL	CIRCUIT			A
8	TE DIM	DB-4 - L9			A
9	TE DIM				A
10	TE DIM				A
11	TE DIM				A
CONTROL MODULE 7					A
TYPE:		LUMILINK LL-D2PH-4C-DIN			A
DESCRIPTION		4 CHANNEL DALI TRAILING EDGE PHASE DIMMER			A
LOCATION		DIN RAIL MOUNTED WITHIN DB-4			A
CHANNEL	CONTROL	CIRCUIT			A
12	TE DIM	DB-4 - L10			A
13	TE DIM				A
14	TE DIM				A
15	TE DIM				A
CONTROL MODULE 8					A
TYPE:		ZENCONTROL ZC-CONTROLLER-PRO-3			A
DESCRIPTION		3 LINE DALI APPLICATION CONTROLLER			A
LOCATION		DIN RAIL MOUNTED WITHIN DB-4			A
BUS:		A			A
CHANNEL	CONTROL	CIRCUIT			A
16	DALI DIM	DB-4 - L11 AND L12			A
17	DALI DIM	DB-4 - L13 AND L14			A
18	DALI DIM	DB-A4- L15			A
CONTROL MODULE 9					A
TYPE:		ZENCONTROL ZC-PSU			A
DESCRIPTION		DALI POWER SUPPLY			A
LOCATION		DIN RAIL MOUNTED WITHIN DB-A			A



ELECTRICAL DESIGN GROUP

ELECTRICAL BUILDING SERVICES CONSULTANTS

P.O. Box 15, SHERWOOD Q. 4075

Phone: (07) 3278 4375 Fax: (07) 3716 0222

Web Site: www.edg.net.au Email: brisbane@edg.net.au


C3770a - FEDERAL HOTEL, TOOWOOMBA

C3770a-0004(A).xls

LIGHTING CONTROL SCHEDULE

REVISION A - 14 AUGUST 2026

CONTROL MODULE 10				A
TYPE:		ZENCONTROL ZC-PSU		A
DESCRIPTION		DALI POWER SUPPLY		A
LOCATION		DIN RAIL MOUNTED WITHIN DB-A		A
CONTROL MODULE 11				A
TYPE:		ZENCONTROL ZC-PSU		A
DESCRIPTION		DALI POWER SUPPLY		A
LOCATION		DIN RAIL MOUNTED WITHIN DB-A		A
CONTROL MODULE 12				A
TYPE:		LUMILINK LL-D2PH-4C-DIN		A
DESCRIPTION		4 CHANNEL DALI TRAILING EDGE PHASE DIMMER		A
LOCATION		DIN RAIL MOUNTED WITHIN DB-4		A
CHANNEL	CONTROL	CIRCUIT		A
19	TE DIM	DB-4 - L16		A
20	TE DIM			A
21	TE DIM			A
22	TE DIM			A



ELECTRICAL DESIGN GROUP

ELECTRICAL BUILDING SERVICES CONSULTANTS

P.O. Box 15, SHERWOOD Q. 4075

Phone: (07) 3278 4375 Fax: (07) 3716 0222

Web Site: www.edg.net.au Email: brisbane@edg.net.au

C3770a - FEDERAL HOTEL, TOOWOOMBA

C3770a-0004(A).xls

LIGHTING CONTROL SCHEDULE

REVISION A - 14 AUGUST 2026

CONTROL MODULE 13				A
TYPE:		LUMILINK LL-D2PH-4C-DIN		A
DESCRIPTION		4 CHANNEL DALI TRAILING EDGE PHASE DIMMER		A
LOCATION		DIN RAIL MOUNTED WITHIN DB-4		A
CHANNEL	CONTROL	CIRCUIT		A
23	TE DIM	DB-4 - L16		A
24	TE DIM			A
25	TE DIM			A
26	TE DIM			A
CONTROL MODULE 14				A
TYPE:		ZENCONTROL 4 CHANNEL DALI RELAY CONTROLLER		A
DESCRIPTION		4 CHANNEL DALI RELAY CONTROLLER		A
LOCATION		DIN RAIL MOUNTED WITHIN DB-4		A
CHANNEL	CONTROL	CIRCUIT		A
27	SWITCH	DB-4- L17		A
28	SWITCH			A
29	SWITCH			A
30	SWITCH			A
CONTROL MODULE 15				A
TYPE:		ZENCONTROL 4 CHANNEL DALI RELAY CONTROLLER		A
DESCRIPTION		4 CHANNEL DALI RELAY CONTROLLER		A
LOCATION		DIN RAIL MOUNTED WITHIN DB-4		A
CHANNEL	CONTROL	CIRCUIT		A
31	SWITCH	DB-4 - L18		A
32	SWITCH			A
33	SWITCH			A
34	SWITCH			A



ELECTRICAL DESIGN GROUP

ELECTRICAL BUILDING SERVICES CONSULTANTS

P.O. Box 15, SHERWOOD Q. 4075

Phone: (07) 3278 4375

Website: www.edg.net.au Email: brisbane@edg.net.au

C3770a - FEDERAL HOTEL, TOOWOOMBA

C3770a-0005(A).xls

DISTRIBUTION BOARD DB-1B

REVISION A - 14 AUGUST 2026

							REV
REPLACE THE EXISTING LC-1 WITH DB-1B AS PER THE ELEVATION AND THE NOTES							A
CIRC	PH	CIRCUIT BREAKER (amps)	CONTROL EQUIPMENT	CABLE SIZE (mm2)	LOCATION	CIRCUIT USE	A
P1	1	25	RCBO	4.0	KITCHEN	CONVEYER OVEN	A
P2	1	20	RCBO	2.5	KITCHEN	REF	A
P3	1	25	RCBO	4.0	KITCHEN	CONVEYER OVEN	A
P4	1	20	RCBO	2.5	KITCHEN	FRYER STARTER	A
P5	1	20	RCBO	2.5	KITCHEN	MW	A
P6	1	20	RCBO	2.5	KITCHEN	DW	A
P7	3	20	RCBO	2.5	KITCHEN	3.5KW OVEN	A
P8	1	20	RCBO	2.5	KITCHEN	TOASTER	A
P9	1	20	RCBO	2.5	KITCHEN	MW	A
P10	1	20	RCBO	2.5	KITCHEN	ICE MACHINE	A
P11	3	40	RCBO	10.0	KITCHEN	20.5KW OVEN	A
P12	3	20	RCBO	2.5	KITCHEN	10.5KW OVEN	A
P13	1	20	RCBO	2.5	SPORTS BAR	LED SCREEN	A
							A
							A
							A



ELECTRICAL DESIGN GROUP

ELECTRICAL BUILDING SERVICES CONSULTANTS

P.O. Box 15, SHERWOOD Q. 4075

Phone: (07) 3278 4375

Website: www.edg.net.au Email: brisbane@edg.net.au

C3770a - FEDERAL HOTEL, TOOWOOMBA

C3770a-0006(A).xls

DISTRIBUTION BOARD DB-4

REVISION A - 14 AUGUST 2026


							REV	
FAULT CURRENT:		6kA UTILISING CASCADING			MAIN SWITCH:		160A NON AUTO LOAD BREAK SWITCH	
CHASSIS SIZE:		60 POLES			SUPPLIED FROM:			A
CHASSIS RATING:		250A			SUPPLY CABLE:			A
PHASES:		3						A
PROVIDE THE DB WITH A FULL WIDTH EMPTY DIN RAIL TO ACCOMMODATE FUTURE CONTACTORS AND CONTROLS IN ADDITION TO THE INITIAL CONTROL EQUIPMENT. PROVIDE THE DB WITH AN AS2293 EMERGENCY LIGHTING CONTROL SYSTEM TO CONTROL THE ASSOCIATED EMERGENCY LIGHTS. PROVIDE THE DB WITH SURGE PROTECTION. PROVIDE A SHOP DRAWING INCLUDING THE LIGHTING CONTROL EQUIPMENT.							A	
CIRC	PH	CIRCUIT BREAKER (amps)	CONTROL EQUIPMENT	CABLE SIZE (mm2)	LOCATION	CIRCUIT USE	A	
P1	1	20	RCBO	2.5	GAMING	CLEANING	A	
P2	1	20	RCBO	2.5	GAMING	TV	A	
P3	1	20	RCBO	2.5	GAMING	SIMTEC LED	A	
P4	1	20	RCBO	2.5		ATM	A	
P5	1	20	RCBO	2.5		TV	A	
							A	
							A	
							A	
							A	
							A	
L1	1	20	RCBO	2.5		LIGHTING	A	
L2	1	20	RCBO	2.5		LIGHTING	A	
L3	1	20	RCBO	2.5		LIGHTING	A	
L4	1	20	RCBO	2.5		LIGHTING	A	
L5	1	20	RCBO	2.5		LIGHTING	A	
L6	1	20	RCBO	2.5		LIGHTING	A	
L7	1	20	RCBO	2.5		LIGHTING	A	
L8	1	20	RCBO	2.5		LIGHTING	A	
L9	1	20	RCBO	2.5		LIGHTING	A	
L10	1	20	RCBO	2.5		LIGHTING	A	
L11	1	20	RCBO	2.5		LIGHTING	A	
L12	1	20	RCBO	2.5		LIGHTING	A	
L13	1	20	RCBO	2.5		LIGHTING	A	
L14	1	20	RCBO	2.5		LIGHTING	A	
L15	1	20	RCBO	2.5		LIGHTING	A	
L16	1	20	RCBO	2.5		LIGHTING	A	
L17	1	20	RCBO	2.5		LIGHTING	A	
L18	1	20	RCBO	2.5		LIGHTING	A	
							A	
							A	
							A	
							A	
							A	
							A	
							A	

LEGEND


- ELECTRICAL SERVICES SWITCHBOARD.
- SWITCHBOARD / CONTROL PANEL NOT PROVIDED AS PART OF THE ELECTRICAL SUBCONTRACT.
- SINGLE POWER OUTLET.
- DOUBLE POWER OUTLET.
- SIGNAGE CONNECTION.
- SINGLE PHASE ISOLATOR.
- THREE PHASE ISOLATOR.
- CONDUIT ROUTE.
- LIGHTING CONTROL SWITCHPANEL, TYPE x.
- ONE WAY LIGHT SWITCH.
- CIRCUIT LINE.
- SWITCH LINE.
- POWER CIRCUIT DESIGNATION.
DENOTES DB AND CIRCUIT.
- LIGHTING CONTROL CHANNEL REFERENCE.
- ELECTRICAL EQUIPMENT AS NOTED.
- REFER TO DETAIL NOTED FOR THE AREA SHOWN HATCHED.
ADDITIONAL OUTLETS & FITTINGS MAY BE SHOWN ON DETAIL.
- Sx: LED JOINERY / CEILING STRIP LIGHT, TYPE AS NOTED.
- Px: DECORATIVE PENDANT, TYPE AS NOTED.
- E1: GENERAL CEILING RECESSED LED EMERGENCY LIGHT, BLACK.
- E2: GENERAL CEILING RECESSED LED EMERGENCY LIGHT, WHITE.
- EX: EMERGENCY LED EXIT LIGHT, WHITE.
- EX BK: EMERGENCY LED EXIT LIGHT, BLACK.
- L1: BISTRO BAR BULKHEAD LED STRIP LIGHT.
- L2: GAMING BAR BULKHEAD LED STRIP LIGHT.
- L3: GAMING CURTAIN PELMET LED STRIP LIGHT.
- L4: GAMING CEILING FEATURE LED STRIP LIGHT.
- L5: SPORTS BAR JOINERY LED STRIP LIGHT.
- L6: RECESSED DOWNLIGHT, WHITE.
- L7: RECESSED DOWNLIGHT, BLACK.
- L8: RECESSED DOWNLIGHT, WHITE.
- L9: RECESSED DOWNLIGHT, BLACK.
- L10: 1200 x 300 RECESSED FLAT PLATE, WHITE TRIM.
- WL01: DECORATIVE WALL LIGHT.
- WL02: EXISTING WALL LIGHT REPLACED WITH NEW.
- WL03: DECORATIVE WALL LIGHT.
- WL04: DECORATIVE WALL LIGHT.
- WL05: EXISTING HIGH LEVEL WALL LIGHT REPLACED WITH NEW.
- HE1: EXISTING HEATER AND CONTROLS TO BE RETAINED.

LEGEND

- P1: DECORATIVE PENDANT.
- P2: DECORATIVE PENDANT.
- P3: DECORATIVE PENDANT.
- P4: DECORATIVE PENDANT.
- P5: CLUSTER OF FOUR DECORATIVE PENDANTS.




DETAIL
DB-1 / LC-1 / DB-1B ELEVATION
NOT TO SCALE



SITE PLAN
FEDERAL HOTEL
SCALE 1:250

EQUIPMENT:


- TEST - TEST PUSH BUTTON MOUNTED ON THE DISTRIBUTION BOARD ESCUTCHEON.
- RESET - RESET PUSH BUTTON MOUNTED ON THE DISTRIBUTION BOARD ESCUTCHEON.
- LAMP - AMBER TEST INDICATING LAMP MOUNTED ON THE DISTRIBUTION BOARD ESCUTCHEON.
- Ta - ADJUSTABLE 0-3 HOUR TIMED RELAY.
- Tb - 15 MINUTE RUN-ON TIMER TO OPERATE UPON THE RETURN OF MAINS POWER.
- Cx - CONTACTOR x.
- CRx - CONTROL RELAY x.
- Rx - RELAY x.



NOTES

- THE EMERGENCY LIGHT UNSWITCHED ACTIVE / GENERAL LIGHTING SWITCHED ACTIVE CIRCUIT ARRANGEMENT AND CONTROL IS TYPICAL FOR ALL CIRCUITS SUPPLYING EMERGENCY LIGHTS.
- PROVIDE ADDITIONAL CONTROL RELAYS (CRx) CONFIGURED AS PER CRa AND CRb FOR ALL ADDITIONAL LIGHTING CIRCUITS THAT SUPPLY LIGHTS IN THE VICINITY OF THE EMERGENCY LIGHTS.

SCHEMATIC
EMERGENCY LIGHTING
NOT TO SCALE



DETAIL
TYPICAL OUTLET MOUNTINGS
NOT TO SCALE

NOTES

1. EXTENT OF WORKS

THE ELECTRICAL SERVICES SUB-CONTRACT INCLUDES BUT IS NOT LIMITED TO THE FOLLOWING:

- SUPPLY AND INSTALLATION OF ALL COMPONENTS FORMING PART OF THE ELECTRICAL SERVICES.
- INSPECTIONS.
- TESTING AND COMMISSIONING.
- MAINTENANCE.
- CABLING, CABLE SUPPORT SYSTEMS AND ACCESS.
- POWER DISTRIBUTION.
- LIGHTING.
- MODIFICATION, RELOCATION AND EXTENSION AS NECESSARY OF ALL EXISTING SERVICES THAT ARE IMPACTED BY THE WORKS OR REQUIRED TO BE IMPENDED BY THE WORKS.
- REMOVAL OF ALL EXISTING SERVICES MADE REDUNDANT BY THE WORKS.
- DOCUMENTS.
- ANY TEMPORARY WORKS REQUIRED TO KEEP THE HOTEL OPERATING DURING THE CONSTRUCTION PROCESS AND ACCOMMODATE STAGING OF THE WORKS TO REFLECT THE EXECUTION OF THE MAIN CONTRACT WORKS.
- ALL MINOR COMPONENTS AND INCIDENTAL WORKS NOT SPECIFICALLY REFERRED TO, HOWEVER NECESSARY TO COMPLETE THE ELECTRICAL SERVICES INSTALLATION SUCH THAT IT IS HANDED OVER COMPLETE, OPERATIONAL AND FIT FOR THE INTENDED USE.

PRIOR TO COMMENCING WORK CONSULT SITE MANAGEMENT FOR ANY HAZARDOUS MATERIAL AND OR ASBESTOS REGISTERS AS WELL AS UNDERTAKE A THOROUGH INSPECTION OF THE SITE TO IDENTIFY ANY POTENTIAL HAZARDOUS MATERIALS, ASBESTOS AND HEALTH OR SAFETY RISKS. ADVISE THE CONTRACTOR OF ANY POTENTIAL HAZARDOUS MATERIALS, ASBESTOS AND HEALTH OR SAFETY RISKS IF IDENTIFIED AND DO NOT COMMENCE WORK UNTIL AN APPROPRIATE MANAGEMENT PLAN HAS BEEN DEVELOPED AND AGREED TO BY ALL PARTIES.

SUPPLY ALL LABOUR, MATERIALS, EQUIPMENT, AND ALL OTHER ITEMS, WHETHER MENTIONED IN DETAIL OR NOT, REQUIRED FOR THE SATISFACTORY COMPLETION OF THE ELECTRICAL SERVICES INSTALLATION, LEAVING IN FULL WORKING ORDER TO THE SATISFACTION OF THE PROJECT MANAGER.

ACCEPT FULL RESPONSIBILITY FOR LIASING, ARRANGING AND CO-ORDINATION OF ALL WORKS THAT HAVE AN EFFECT ON OR WILL BE AFFECTED BY THE ELECTRICAL SERVICES.

REFER TO THE EQUIPMENT SCHEDULE FOR ADDITIONAL REQUIREMENTS.

2. WORKMANSHIP

ENSURE THAT THE ELECTRICAL WORK IS PERFORMED BY THE HOLDER OF A CURRENT ELECTRICAL SUB CONTRACTOR LICENSE AND THE SERVICES COVERED BY THE ACMA IS PERFORMED BY THE HOLDER OF THE APPROPRIATE CURRENT ACMA LICENSE. ENSURE THE INSTALLATION AND ALL COMPONENTS, FIXTURES, FITTINGS, OUTLETS AND CABLES ARE SUPPLIED AND INSTALLED TO A HIGH STANDARD THROUGHOUT, AND INSTALLED IN A NEAT AND TRADESMAN LIKE MANNER, TO THE CURRENT INDUSTRY STANDARDS. ENSURE ALL MATERIALS AND COMPONENTS OF A SIMILAR TYPE ARE OF THE SAME MANUFACTURER AND INSTALLED IN A UNIFORM MANNER.

IT IS THE ELECTRICAL SUB CONTRACTOR'S RESPONSIBILITY TO ENSURE THAT THE INSTALLATION IS FIT FOR PURPOSE AND IS PROVIDED AS A COMPLETE WORKING INSTALLATION. IT IS THE ELECTRICAL SUB CONTRACTOR'S RESPONSIBILITY TO PROVIDE ALL COMPONENTS, FITTINGS, FIXTURES, SYSTEMS, PROGRAMMING ETC IRRESPECTIVE OF THE LEVEL DETAILED IN THE DOCUMENTS SUCH THAT THE INSTALLATION IS PROVIDED AS A COMPLETE WORKING INSTALLATION.

CONCEAL ALL WIRING AND CONDUITS. EXPOSED CABLING OR CONDUITS ARE GENERALLY NOT ACCEPTABLE. IT IS NOTED THAT CHASING AND REINSTATEMENT WILL BE REQUIRED. ENSURE ALL COMPONENTS, EQUIPMENT AND MATERIALS SUPPLIED ARE NEW, UNUSED, DESIGNED AND SELECTED TO ENSURE SATISFACTORY OPERATION UNDER VARYING ATMOSPHERIC, CLIMATIC, HUMID TROPICAL CONDITIONS WITHOUT DISTORTION AND DETERIORATION IN ANY PART AFFECTING EFFICIENCY AND RELIABILITY OF THE SYSTEMS. DESIGN AND SELECT ALL EQUIPMENT TO PROVIDE THE NECESSARY SAFETY TO HUMAN LIFE AND PROPERTY DURING OPERATION AND MAINTENANCE WITH PARTICULAR ATTENTION GIVEN TO ELECTRICAL SAFETY AND SEGREGATION PRECAUTIONS.

CHECK THE FINISHED PAINTWORK AROUND THE AREA OF EACH INSTALLATION AND TOUCH UP ALL DAMAGED PARTS AND FINISHES AFTER THE INSTALLATION OF THE ELECTRICAL SERVICES.

ALL WORKS ARE TO BE CARRIED OUT IN ACCORDANCE WITH THE BUILDER'S PROGRAM. ENSURE ALL FINAL LOCATIONS OF OUTLETS AND FITTINGS ARE CO-ORDINATED ONSITE WITH THE ARCHITECT AND ALL OTHER SERVICES, TO THE APPROVAL OF THE PROJECT MANAGER. ALLOW TO CO-ORDINATE THE FINAL LOCATION OF ALL EQUIPMENT, FITTINGS, & OUTLETS, SUCH THAT THEY ARE INSTALLED IN ACCORDANCE WITH THE AS3000 RESTRICTED ZONES, AND ARE NOT COVERED INAPPROPRIATELY.

ENSURE THAT ALL METAL SURFACES ARE SUITABLY PROTECTED AGAINST CORROSION, AND THAT ALL PLASTIC MATERIALS ARE UV STABILISED.

PROVIDE ALL MATERIALS AS NEW, AND OF THE HIGHEST CLASS AVAILABLE FOR THEIR RESPECTIVE TYPES. ENSURE ALL ASPECTS OF THE WORK ARE OF A HIGH STANDARD THROUGHOUT, AND INSTALLED IN A NEAT AND TRADESMAN LIKE MANNER, TO THE CURRENT INDUSTRY STANDARDS.

MODIFICATION, RELOCATION AND EXTENSION AS NECESSARY OF ALL EXISTING SERVICES THAT ARE IMPACTED BY THE WORKS OR REQUIRED TO BE EXTENDED BY THE WORKS.

PROVIDE ALL TEMPORARY WORKS REQUIRED TO KEEP THE VENUE AND ALL CONSTRUCTION STAGES OPERATING INCLUDING STAGED COMMISSIONING DURING THE CONSTRUCTION PROCESS.

ALL MINOR COMPONENTS AND INCIDENTAL WORKS NOT SPECIFICALLY REFERRED TO, HOWEVER NECESSARY TO COMPLETE THE ELECTRICAL SERVICES INSTALLATION SUCH THAT IT IS HANDED OVER COMPLETE, OPERATIONAL AND FIT FOR THE INTENDED USE.

CORRUGATED CONDUITS MUST NOT BE USED WITHIN ANY FOOD OR DRINK PREPARATION OR SERVERY AREAS.

CABLE JOINS ARE NOT ACCEPTABLE. ALL CABLING, WIRING, CONDUCTORS AND CONDUITS MUST BE CONCEALED. ALL EXISTING ELECTRICAL SERVICES INCLUDING CABLING AND SWITCHGEAR THAT IS FOUND TO BE REDUNDANT OR MADE REDUNDANT BY THE WORKS MUST BE REMOVED.

IT IS ACCEPTABLE TO USE EXISTING SWITCHGEAR, OUTLETS AND CABLING IF THEY ARE APPROPRIATELY RATED AND THE ELECTRICIAN ACCEPTS RESPONSIBILITY OVER THE SWITCHGEAR / OUTLETS / CABLE AND PROVIDES A WARRANTY OVER IT AS IF IT WAS INSTALLED NEW BY THE ELECTRICIAN.

3. STANDARDS

IRRESPECTIVE OF INFORMATION CONTAINED IN THE ELECTRICAL SERVICES DOCUMENTS OR IN INSTRUCTIONS, IT IS THE ELECTRICAL SUB CONTRACTORS RESPONSIBILITY TO ENSURE ALL ELECTRICAL SERVICES WORKS ARE INSTALLED IN ACCORDANCE WITH THE REQUIREMENTS OF THE FOLLOWING. REFER ANY DISCREPANCIES BETWEEN THE REQUIREMENTS OF THE FOLLOWING AND/OR THE ELECTRICAL SERVICES DOCUMENTS AND INSTRUCTIONS TO THE ARCHITECT FOR CLARIFICATION PRIOR TO THE PLACING OF ORDERS, FABRICATION OR INSTALLATION OF THE ITEMS/METHODS IN DISCREPANCY.

- NCC BUILDING CODE OF AUSTRALIA.
- ELECTRICITY ACT.
- ELECTRICAL SAFETY ACT.
- AS/NZS3000.
- AS3008.
- WORKPLACE HEALTH AND SAFETY ACT.
- TELECOMMUNICATIONS ACT.
- ACMA REQUIREMENTS.

NOTES

4. AUTHORITIES

ENSURE ALL OF THE ELECTRICAL SERVICES COMPLY WITH THE REQUIREMENTS OF ALL REGULATORY AUTHORITIES HAVING JURISDICTION OVER THE SITE INCLUDING BUT NOT LIMITED TO THE FOLLOWING:

- ACMA.
- LOCAL COUNCIL.
- LOCAL SUPPLY AUTHORITY.
- STATE GOVERNMENT DEPARTMENT OF ENVIRONMENT AND HERITAGE.
- QLD GOVERNMENT, DIVISION OF WORKPLACE, HEALTH AND SAFETY.
- QLD FIRE AND EMERGENCY SERVICES.

5. DOCUMENTATION

WITHIN TWO WEEKS OF PRACTICAL COMPLETION PROVIDE THE FOLLOWING DOCUMENTATION.

AS CONSTRUCTED DRAWINGS INCLUDING:

- ELECTRICIANS NAME AND CONTACT DETAILS.
- PROJECT NAME, ADDRESS AND DATE OF PRACTICAL COMPLETION.
- FITTING POSITIONS AND TYPES CROSS REFERENCED TO A FITTING / EQUIPMENT SCHEDULE.
- OUTLET, SWITCH, AND CONNECTION POSITIONS CROSS REFERENCED TO A FITTING / EQUIPMENT SCHEDULE.
- REMOTE DRIVER LOCATIONS.
- CIRCUITS CROSS REFERENCED TO A DISTRIBUTION BOARD SCHEDULE.
- LIGHTING CONTROL CHANNELS CROSS REFERENCED TO A LIGHTING CONTROL SCHEDULE.
- POWER SCHEMATIC.
- SWITCHBOARD SHOP DRAWINGS.
- CABLE ACCESS ROUTES.

A FITTING / EQUIPMENT SCHEDULE INCLUDING.

- FITTING DETAILS INCLUDING THE MANUFACTURERS CATALOGUE NUMBERS WITH THE TYPES CROSS REFERENCED TO THE AS CONSTRUCTED DRAWINGS.
- OUTLETS AND SWITCHES INCLUDING THE MANUFACTURERS CATALOGUE NUMBERS WITH THE TYPES CROSS REFERENCED TO THE AS CONSTRUCTED DRAWINGS.

DISTRIBUTION BOARD SCHEDULES CROSS REFERENCED TO THE AS CONSTRUCTED DRAWINGS.

LIGHTING CONTROL SCHEDULE CROSS REFERENCED TO THE AS CONSTRUCTED DRAWINGS.

PHOTOS OF EACH SWITCHBOARD INCLUDING:

- CLOSED POSITION SUCH THAT THE SWITCHBOARD DESIGNATION AND CLEARANCE IS VISIBLE.
- THE SUBMAIN LABEL.
- DOOR/S OPEN ESCUTCHEON/S CLOSED SUCH THAT THE SPARE CAPACITY AND LABELLING IS VISIBLE.
- DOOR/S OPEN ESCUTCHEON/S REMOVED SUCH THAT THE SWITCHGEAR AND INTERNAL CABLING IS VISIBLE.

6. CABLES

UNLESS OTHERWISE SPECIFIED, INSTALL AND TERMINATE CABLES IN ACCORDANCE WITH THE MANUFACTURERS' RECOMMENDATIONS. DETERMINE THE FINAL ROUTES TO SUIT THE BUILDING STRUCTURE AND SITE CONDITIONS. UNLESS NOTED OTHERWISE, PROVIDE ALL 240 VOLT POWER AND LIGHTING WIRING AS 2.5mm² TWIN & EARTH STRANDED COPPER CONDUCTORS, PVC INSULATED 0.6/1kV V75 GRADE TO AS3174, PROTECTED BY A 20 AMP CIRCUIT BREAKER. ALL CONDUIT AND FITTINGS TO BE RIGID UPVC TO AS2053, UNLESS NOTED OTHERWISE.

7. POWER DISTRIBUTION

PROVIDE A NEW DISTRIBUTION BOARD DB-4. PROVIDE A NEW 100 AMP THREE PHASE MCCB IN THE EXISTING HOTEL MAIN SWITCH BOARD AND A NEW SUBMAIN TO SUPPLY DB-4 VIA A 4C+E 55mm Cu XLPE/PVC SUBMAIN.

THE EXISTING LC-1 IS TO BE REPLACED WITH AN EXTENSION TO THE EXISTING DISTRIBUTION BOARD DB-1 TO BE KNOWN AS DB-1B.

ALL SWITCHBOARDS AND SWITCHGEAR ARE TO BE SCHNEIDER OR NHP AND CONTAIN AT LEAST 25% OR 12 SPARE POLES (WHICHEVER IS THE LARGER) AT PRACTICAL COMPLETION. ALL SWITCHBOARDS ARE TO BE LIGHT GREY. ORANGE SWITCHBOARDS ARE NOT ACCEPTABLE. PROVIDE 92268 KEY LOCKABLE DOORS ON ALL SWITCHBOARDS. ALL SWITCHBOARDS AND CIRCUITS MUST BE UNIQUELY NAMED WITH SWITCHBOARDS PROVIDED WITH A LABEL CONTAINING:

- SOURCE NAME.
- SOURCE OVERLOAD RATING IN AMPS.
- SUBMAIN CABLE TYPE, SIZE, CONFIGURATION AND LENGTH.

ALL REMOVABLE PANELS AND ESCUTCHEONS MUST BE SECURED VIA 1/4 TURN LATCHES THAT REMAIN PART OF THE PANEL / ESCUTCHEON. IT IS NOT ACCEPTABLE TO SECURE REMOVABLE PANELS AND ESCUTCHEONS BY BOLTS, NUTS OR SCREWS.

ALL CIRCUIT BREAKERS AND CIRCUIT SCHEDULES MUST BE LABELLED / CONTAIN THE SUBMAIN / CIRCUIT USE AND LOCATION SUCH THAT THE CONNECTION / OUTLET CAN BE SIMPLY IDENTIFIED.

OUTLETS ARE TO BE PROVIDED WITH A NEAT HAND WRITTEN CIRCUIT DESIGNATION BY INDELIBLE INK ON THE FACEPLATE SUCH THAT IT IS NOT VISIBLE WHEN THE COVER IS CONCEALED.

REFER TO THE DISTRIBUTION BOARD SCHEDULES FOR ADDITIONAL REQUIREMENTS AND CIRCUIT DETAILS.

ENSURE ALL THREE PHASE CIRCUITS ARE PROVIDED WITH CORRECT PHASE ROTATION.

ENSURE ALL OUTLETS AND ISOLATORS ARE POSITIONED SUCH THAT THEY ARE NOT COVERED BY THE EQUIPMENT. THE FINAL POSITION OF ALL OUTLETS AND ISOLATORS ARE TO BE CONFIRMED ON SITE BY THE TENANTS REPRESENTATIVE.

NOTES

8. GAMING

THE GAMING ELECTRICIAN WILL BE ENGAGED DIRECTLY BY ENDEAVOUR GROUP TO UNDERTAKE THE FOLLOWING:

- COMMUNICATIONS CABLING.
- GAMING DB.
- CIRCUIT BREAKER IN DB-A AND CIRCUIT TO THE GAMING DB (DB-G).
- CIRCUITS FROM THE GAMING DB AS NECESSARY TO:
 - GAMING MACHINES.
 - GAMING MODEMS.
 - GAMING MACHINE SIGNAGE.
 - GAMING ROOM CRTS.
 - TAB OUTLETS.
- GAMING ROOM CABLE ACCESS EXCLUDING FLOOR CHASES AND REINSTATEMENT OF THE FLOOR CHASES.

ALL OTHER REMAINING ELECTRICAL SERVICES WITHIN THE GAMING ROOM ARE TO BE PROVIDED AS PART OF THE BUILDING WORKS ELECTRICAL SUB CONTRACT.

9. LIGHTING

THE EXISTING LIGHTING CONTROL SYSTEM IS TO BE REMOVED INCLUDING THE BOARDS LC-1 AND LC-3. ALL EXISTING LIGHTS THAT REMAIN THAT ARE SUPPLIED VIA LC-1 AND LC-3 ARE TO BE RESUPPLIED FROM DB-4 WITH NEW SWITCHGEAR AND CONTROLS.

ALL FRONT OF HOUSE LIGHTING IS TO BE 2,700K OR 3,000K AND THE BACK OF HOUSE LIGHTING IS TO BE 4,000K.

UNLESS A FITTING HAS BEEN SPECIFIED IN THE EQUIPMENT SCHEDULE THAT CONTAINS A MAIN VOLTAGE LAMP, ALL LIGHT FITTINGS MUST BE PROVIDED AS SOLID-STATE LED WITH A FIVE-YEAR MANUFACTURERS REPLACEMENT WARRANTY AND A MINIMUM TWO YEAR MANUFACTURERS REPLACEMENT AND LABOUR WARRANTY.

ALL FRONT OF HOUSE LIGHTS THAT DO NOT CONTAIN A MAIN VOLTAGE LAMP ARE TO BE DALI DIMMABLE.

REMOTE DRIVERS ARE TO BE USED IF POSSIBLE AND LOCATED IN A CONCEALED ACCESSIBLE POSITION. IF THE DRIVER CAN NOT BE REACHED FROM THE FITTING ITS POSITION MUST BE NOTED ON THE AS CONSTRUCTED DOCUMENTS.

ALL FRONT OF HOUSE LIGHTS THAT CONTAIN MAIN VOLTAGE LAMPS ARE TO BE PROVIDED WITH THE LOWEST OUTPUT PRACTICAL TO ACHIEVE THE REQUIRED ILLUMINATION / EFFECT AND BE TRAILING EDGE PHASE DIMMABLE.

ALL ILLUMINATED SIGNAGE, GAMING BASE FOOTREST LEDS, CARPARK LIGHTS, AND EXTERNAL SECURITY LIGHTS NOT CONSIDERED FRONT OF HOUSE ARE TO BE SWITCHED.

ALL LIGHTING CIRCUITS MUST BE PROTECTED BY A 20 AMP RCBO WITH THE AVERAGE NUMBER OF FITTINGS / DRIVERS SUPPLIED FROM A SINGLE CIRCUIT NOT EXCEEDING 25 WITH THE MAXIMUM NOT EXCEEDING 30.

PROVIDE A ZEN CONTROL LIGHTING CONTROL SYSTEM TO CONTROL THE LIGHTING CONFIGURED WITH THE FOLLOWING SCENES:

INTERNAL

- CLEANING - MANUAL OPERATION. 100% LIGHTS ON AND SIGNS OFF.
- DAY - AUTOMATIC OPERATION FROM 10.00 AM TO 3.30 PM.
- AFTERNOON - AUTOMATIC OPERATION FROM 3.30 PM TO DUSK.
- EVENING - AUTOMATIC OPERATION FROM DUSK TO 8.30 PM.
- NIGHT - AUTOMATIC OPERATION FROM 8.30 PM TO CLOSING.
- CLOSED - MANUAL OPERATION. 100% ON FOR 15 MINUTES THEN TO A SECURITY MODE.

EXTERNAL

- DAY - AUTOMATICALLY OFF FROM DAWN TO DUSK.
- NIGHT - AUTOMATICALLY ON FROM DUSK UNTIL 15 MINUTES PAST CLOSING.
- CLOSED - MANUAL OPERATION. NIGHT MODE FOR 15 MINUTES THEN TO A SECURITY MODE.

SET THE ILLUMINATION LEVELS IN CONSULTATION WITH THE VENUE MANAGER AND OBTAIN WRITTEN APPROVAL FROM THE VENUE MANAGER OF THEIR ACCEPTANCE OF THE ILLUMINATION SCENE LEVELS FOR EACH STAGED HANDOVER AND SUBMIT A COPY OF THE APPROVAL TO THE ARCHITECT.

EACH FUNCTIONAL AREA IS TO BE PROVIDED WITH A SWITCHPANEL IN A NON-CUSTOMER ACCESSIBLE POSITION WITH THE ABILITY TO MANUALLY INSTIGATE THE ABOVE SCENES.

DIN RAIL MOUNT THE LIGHTING CONTROL EQUIPMENT WITHIN DB-4.

ALL OF THE LIGHT FITTINGS, LAMPS AND ACCESSORIES ARE TO BE PROVIDED AS PART OF THIS CONTRACT. THE LIGHTING COMPONENT OF THIS CONTRACT INCLUDES, BUT IS NOT LIMITED TO THE FOLLOWING EXTENT OF WORK:

- LIGHTING.
- LIGHT FITTINGS AND ACCESSORIES.
- EMERGENCY AND EXIT LIGHTING.
- EARTHING OF THE LIGHTING INSTALLATION.
- LIGHTING CONTROL.
- ZEN CONTROL LIGHTING CONTROL SYSTEM.
- LIGHTING SUBCIRCUITS.
- TESTING AND COMMISSIONING.
- RECONNECTION OF THE EXISTING LIGHTING THAT REMAINS.
- REMOVAL OF ALL EXISTING REDUNDANT LIGHTING SERVICES INCLUDING THE REDUNDANT LIGHTING CONTROL SYSTEM.

COMMISSION THE LIGHTING CONTROL AT PRACTICAL COMPLETION AND AGAIN THREE TIMES DURING THE DEFECTS AND LIABILITY PERIOD TO THE SATISFACTION OF THE OPERATOR.

NOTES

11. EMERGENCY AND EXIT LIGHTING

WITH THE EXCEPTION OF THE EXISTING KITCHEN EMERGENCY LIGHTS SUPPLIED FROM DB-1 REPLACE THE ENTIRE EMERGENCY LIGHTING SYSTEM WITH A NEW EMERGENCY LIGHTING SYSTEM SUPPLIED FROM DB-4.

PROVIDE A SINGLE POINT EMERGENCY LIGHTING SYSTEM THAT COMPLIES WITH THE LATEST ISSUE OF ALL PARTS AS2293 AND THE RELEVANT PARTS OF THE NCC BCA. INSTALL EMERGENCY LIGHT FITTINGS NOMINATED AS MAINTAINED WITH THE LAMP PERMANENTLY ON SUPPLIED VIA AN UNSWITCHED ACTIVE MAINS SUPPLY WHEN THE MAINS SUPPLY IS AVAILABLE. WHEN THE MAINS SUPPLY IS NOT AVAILABLE, THE LAMP IS TO REMAIN ON SUPPLIED BY THE EMERGENCY PACK. SINGLE LAMP MAINTAINED EMERGENCY LIGHTS ARE NOT SWITCHED WITH THE LOCAL GENERAL AREA LIGHTING. (THE LAMP IS ALWAYS ON.)

INSTALL EMERGENCY LIGHT FITTINGS NOMINATED AS NON-MAINTAINED AS FOLLOWS:

- IF THE FITTING IS NOT BEING SWITCHED, THE LAMP IS TO REMAIN OFF WHEN THE MAINS SUPPLY IS AVAILABLE. WHEN THE MAINS SUPPLY IS NOT AVAILABLE THE LAMP IS TO BE SWITCHED ON SUPPLIED BY THE EMERGENCY PACK. UNSWITCHED SINGLE LAMP NON-MAINTAINED EMERGENCY LIGHTS ARE NOT SWITCHED WITH THE LOCAL GENERAL AREA LIGHTING. (THE LAMP IS ON ONLY WHEN THE MAINS SUPPLY IS NOT AVAILABLE.)
- IF THE FITTING IS BEING SWITCHED, THE LAMP IS TO BE SUPPLIED AND CONTROLLED WITH THE LOCAL GENERAL AREA LIGHTING WHEN THE MAINS SUPPLY IS AVAILABLE. WHEN THE MAINS SUPPLY IS NOT AVAILABLE THE LAMP IS TO BE SWITCHED ON, SUPPLIED BY THE EMERGENCY PACK. (THE LAMP IS ON WHEN TURNED ON WITH THE LOCAL GENERAL LIGHTING OR THE MAIN SUPPLY IS NOT AVAILABLE.)

INSTALL EMERGENCY LIGHTS SUCH THAT THE STATUS INDICATOR L.E.D. IS CLEARLY VISIBLE AND THE TEST BUTTONS ARE READILY ACCESSIBLE. LABEL EACH CIRCUIT BREAKER WHICH CONTROLS THE UNSWITCHED ACTIVE TO EXIT LIGHTS WITH A LABEL FIXED ADJACENT; ENGRAVED PLASTIC LAMINATE, GREEN BACKGROUND WITH WHITE CHARACTERS: -

WARNING
INTERRUPTING SUPPLY WILL DISCHARGE
EMERGENCY LIGHTING BATTERIES

PROVIDE WRITTEN EVIDENCE OF THE INITIAL COMMISSIONING AND TESTING AND TESTING FOR THE DURATION OF THE MAINTENANCE PERIOD IN ACCORDANCE WITH AS 2293.2.


THIS EVIDENCE IS TO BE IN THE FORM OF A LOG BOOK SIMILAR TO THE GENERAL LIGHTING SERVICE PTY LTD "EMERGENCY LIGHTING MAINTENANCE LOG BOOK AND MANUAL" WHICH IS TO BE PROVIDED BY THE ELECTRICAL SUB-CONTRACTOR AND HAVE ALL ENTRIES FULLY COMPLETED AND BE PRESENTED FOR INSPECTION AT PRACTICAL COMPLETION. THE LOG BOOK IS TO BE RETAINED BY THE ELECTRICAL SUB-CONTRACTOR FOR THE DURATION OF THE MAINTENANCE PERIOD, AND THE SIX MONTHLY TEST AND MAINTENANCE RESULTS ENTERED. THE LOG BOOK IS TO BE PRESENTED FOR APPROVAL AT FINAL COMPLETION (EXPIRY OF THE MAINTENANCE PERIOD) AND WILL BE FORWARDED TO THE OPERATOR FOR THEIR USE.

PROVIDE MAINTENANCE OF THE EMERGENCY AND EXIT LIGHTING INSTALLATION INCLUDING RECORDS IN ACCORDANCE WITH THE LATEST ISSUE OF ALL PARTS AS2293 AND THE RELEVANT PARTS OF THE NCC BCA. PROVIDE THE EMERGENCY LIGHTING SYSTEM WITH A SUPPLY SENSING AND TESTING FACILITY IN ACCORDANCE WITH AS 2293.1.

12. ABBREVIATIONS

A	-	AMP CURRENT RATING
AB	-	MOUNT ABOVE BENCH.
AFFL	-	ABOVE FINISHED FLOOR LEVEL.
BB	-	MOUNT BELOW BENCH.
BH	-	MOUNT ON BULKHEAD.
CEIL	-	MOUNT ON CEILING.
CS	-	MOUNT WITHIN CEILING SPACE.
C/W	-	COMPLETE WITH.
DW	-	DISHWASHER.
MCB	-	MINIATURE CIRCUIT BREAKER.
MCCB	-	MOLDED CASE CIRCUIT BREAKER.
MSB	-	MAIN SWITCHBOARD.
MSSB	-	MECHANICAL SERVICES SWITCHBOARD.
MW	-	MICROWAVE.
N	-	NEON / LED INDICATOR WHEN ON.
NTS	-	NOT TO SCALE.
RCBO	-	CIRCUIT BREAKER C/W AN INTEGRAL 30mA RESIDUAL CURRENT DEVICE.
RCD	-	CIRCUIT PROTECTED VIA A 30mA RESIDUAL CURRENT DEVICE.
REF	-	REFRIGERATOR.
UNO	-	UNLESS NOTED OTHERWISE.
WP	-	WEATHERPROOF TO IP56 UNO.
500	-	NUMBER DENOTES MOUNTING HEIGHT AFFL.


ELECTRICAL DESIGN GROUP BRISBANE PTY LTD ACN 092 710 793		THE COPYRIGHT OF THIS DRAWING REMAINS THE PROPERTY OF THE ELECTRICAL DESIGN GROUP.		PROJECT: FEDERAL HOTEL, TOOWOOMBA		A TENDER 14/08/2026	
TRADING AS: ELECTRICAL DESIGN GROUP		USE FIGURED DIMENSIONS IN PREFERENCE TO SCALE.		DRAWING: ELECTRICAL SERVICES NOTES		REV: DESCRIPTION: DATE:	
		ALL DIMENSIONS TO BE VERIFIED ONSITE.		BRISBANE GOLD COAST		DRAWING: ELECTRICAL SERVICES NOTES	
				P.O.Box 15, Sherwood Q.4075 Phone: (07) 3278 4375 Email: brisbane@edg.net.au Web: www.edg.net.au		SCALE: NOT TO SCALE AT A1	
				111 JAMES STREET, TOOWOOMBA CITY, QUEENSLAND		PROJECT NO: C3770a	
						DRAWING NO: E02	
						REVISION: A	



NOTE:





EXISTING ELECTRICAL SERVICES WITHIN THESE DASH LINED AREAS TO BE REMOVED, UNLESS NOTED OTHERWISE.




DETAIL A
BAR FLOOR PLAN
SCALE 1:50

NOTE:
REFER TO DRAWING C3770a-E05.dwg FOR THE
ADDITIONAL JOINERY AND WALL LIGHTING PLAN.






DETAIL A
BISTRO BAR & WALL ELEVATION
SCALE 1: 25




DETAIL E
TYPICAL SEATING S2 STRIP LIGHT SECTION
SCALE 1: 10




PLAN
JOINERY & WALL LIGHTING
SCALE 1: 100



DETAIL C
GAMING BAR & SCREEN ELEVATION
SCALE 1: 25



DETAIL B
GAMING BAR & WALL ELEVATION
SCALE 1: 25



DETAIL D
BISTRO DINING FEATURE WALL ELEVATION
SCALE 1: 25