




NOTE. × if applicable.



- NOTES:**
1. Foundation design details are as follows:
 - * Unstable soils are soft clay to sandy gravel with a soil strength 50 - 150 KPa. These soil types REQUIRE a base slab as shown.
 - * Stable soils are very stiff clay to shale/rock with soil strength of 150KPa or higher. These soil types DO NOT REQUIRE a base slab.
 2. Lift uncivilized and base slab separately with 4 x 1.31 Reid Swiftlift lifting eyes
 3. Position top face of Uncivilized at finished ground level.
(refer Civil construction drawings)
 4. Installed Uncivilized shall be level.
 5. If deep excavation is required under transformer cabinet and in front of foundation, plinth front edge shall be propped while excavation remains open.
 6. Foundation Components:
 - 1 x Uncivilized (Stock Code 19959)
 - 2 x End Walls (Stock Code 19959)
 - 1 x Base Slab (Stock Code 19940)Uncivilized and End Walls come assembled with a Layer of Preformed Sealant to the perimeter of the Uncivilized End and between the Mating Surfaces.
 7. Only require minimum 40mmKraut Kcrete required to pass Conduits (Max. Conduit 50mm Nom. Dia.) or Cables through uncivilized void by tapping out concrete.
 8. Seal between conduits/cables and concrete end wall at knuckle interface by grouting with high strength sand and cement grout after conduit installation to prevent entry of vermin and backfill ingress to uncivilized void.
 9. Refer to property boundaries to facilitate installation of earth grid.
 10. Consumers mains (where present) shall not cross HV mains or run back under transformer.



- NOTE:**
1. Backfill excavated area with crusher dust deco or pit sand and compact in place. Ensuring that only pit sand is used around direct laid cables.
 2. Reinforced concrete surround slab area 5.7m x 4.8m:
 - a) 100/125mm thick slab;
 - b) 11 TM trench mesh reinforcement in centre of slab;
 - c) 25 MPa grade concrete;
 - d) Finish by wood float or by nylon broom.
 3. The top face of the concrete surround slab shall be 25mm above the final surface level (when turf is laid).
 4. The concrete slab is to slope away from plinth falling at a slope of 1 in 25.
 5. Cable aperture through the precast concrete plinth shall be capped to 50mm from the top of plinth.
 - A 30mm deep layer of 1:6 ratio weak mix concrete shall be placed to seal aperture.
 6. The surface of the surround slab may be finished with a stencil pattern surface to match the surrounding pavements of the development. (Use textcrete or equivalent product. Construct to supplier's specifications.)



- Notes:
- (1) Energex Communication conduit to be 100mm white located top kerbside.
 - (2) Power cable conduits to be 125mm orange, light duty.
 - (3) Separation for conduits - 50mm minimum, up to 160mm desirable.
 - (3) Increased cover required for road crossings.
 - (4) Select Backfill and Pit sand bedding complying with ENERGEX UDCM Section C2
 - (5) For de-rating factors for cables in duct bank, refer to the Plant Rating Manual

TYPICAL CROSS SECTION - FOOTPATH ALONG KARRABIN ROSEWOOD ROAD

1. CABLE CONDUIT SHALL BE OF THE FOLLOWING TYPE:
LIGHT DUTY ELECTRICAL CONDUIT TO AS/NZS 2053.
CONDUIT BENDS SHALL HAVE A MINIMUM RADIUS OF 1830mm.
2. CONDUITS SHALL BE 125mm ORANGE FOR ELECTRICAL AND 100MM WHITE (LOCATED TOP KERBSIDE) AS SPECIFIED BY ENERGENX AND SHALL BE SUPPLIED AND INSTALLED BY THE DEVELOPER OR ENERGENX.
CONDUITS SHALL BE SECURELY SEALED TO PREVENT INGRESS OF DIRT UNTIL CABLE INSTALLATION AND THEN RESEALED.
3. EACH CONDUIT TO BE FITTED WITH A 6mm BRAID POLYPROPYLENE DRAW ROPE TO PULL IN HAULAGE ROPE. (MINIMUM BREAKING STRENGTH OF 10kN.)
4. ENERGENX MAY NEED TO INSTALL AN EARTH WIRE AND EARTH RODS IN CONDUIT TRENCHES FROM THE SUBSTATION SITE.
5. ELECTRICITY SUPPLY CONDUITS AND CABLES SHALL HAVE POLYMERIC CABLE PROTECTION COVER STRIPS PLACED 100mm ABOVE THE TOP CONDUIT FACE OF THE ELECTRICITY SUPPLY CONDUITS AND CABLES. CABLE PROTECTION COVER STRIP SHALL BE LAPPED WHEN PLACED TOGETHER, 100mm MINIMUM ALONG THE LONGITUDINAL AXIS, 40mm MINIMUM ALONG THE TRANSVERSE AXIS AND SHALL EXTEND 40mm MINIMUM PAST THE END OF THE CONDUIT/CABLE BANK.
6. POLYMERIC CABLE PROTECTION COVER SHALL BE A 5mm MINIMUM THICKNESS AS DESCRIBED IN THE AUSTRALIAN STANDARD; AS4702 FPR POLYMERIC CABLE PROTECTION COVERS.
7. REDUCED CONDUIT SEPARATION MAY BE ACCEPTED TO AVOID SPECIFIC OBSTACLES
8. MIN. DEPTHS SHOWN ARE THOSE DEPTHS REQUIRED BY CODE OF PRACTICE, WORKS (MINOR ROADS) AND DMR (ARTERIAL ROADS).



- Notes:
- (1) Energex Communication conduit to be 100mm white located top kerbside.
 - (2) Power cable conduits to be 125mm orange, light duty.
 - (3) Separation for conduits - 50mm minimum, up to 160mm desirable.
 - (3) Increased cover required for road crossings.
 - (4) Select Backfill and Pit sand bedding complying with ENERGEX UDCM Section C2
 - (5) For de-rating factors for cables in duct bank, refer to the Plant Rating Manual

TYPICAL CROSS SECTION - ROAD CROSSING

1. CABLE CONDUIT SHALL BE OF THE FOLLOWING TYPE:
LIGHT DUTY ELECTRICAL CONDUIT TO AS/NZS 2053.
CONDUIT BENDS SHALL HAVE A MINIMUM RADIUS OF 1830mm.
2. CONDUITS SHALL BE 125mm ORANGE FOR ELECTRICAL AND 100MM WHITE (LOCATED TOP KERBSIDE) AS SPECIFIED BY ENERGENX AND SHALL BE SUPPLIED AND INSTALLED BY THE DEVELOPER OR ENERGENX.
CONDUITS SHALL BE SECURELY SEALED TO PREVENT INGRESS OF DIRT UNTIL CABLE INSTALLATION AND THEN RESEALED.
3. EACH CONDUIT TO BE FITTED WITH A 6mm BRAID POLYETHYLENE DRAIN ROPE TO PULL IN HAULAGE ROPE. (MINIMUM BREAKING STRENGTH OF 10kN).
4. ENERGENX MAY NEED TO INSTALL AN EARTH WIRE AND EARTH RODS IN CONDUIT TRENCHES FROM THE SUBSTATION SITE.
5. ELECTRICITY SUPPLY CONDUITS AND CABLES SHALL HAVE POLYMERIC CABLE PROTECTION COVER STRIPS PLACED 100mm ABOVE THE TOP CONDUIT FACE OF THE ELECTRICITY SUPPLY CONDUITS AND CABLES.
CABLE PROTECTION COVER STRIP SHALL BE LAPPED WHEN PLACED TOGETHER; 100mm MINIMUM ALONG THE LONGITUDINAL AXIS, 40mm MINIMUM ALONG THE TRANSVERSE AXIS AND SHALL EXTEND 40mm MINIMUM PAST THE EXTERNAL EDGES OF THE CONDUIT/CABLE BANK.
6. POLYMERIC CABLE PROTECTION COVER SHALL BE A MINIMUM OF 5mm THICK AS DESCRIBED IN THE AUSTRALIAN STANDARD; AS54702 FPR POLYMERIC CABLE PROTECTION COVERS.
7. REDUCED CONDUIT SEPARATION MAY BE ACCEPTED TO AVOID SPECIFIC OBSTACLES
8. MIN. DEPTHS SHOWN ARE THOSE DEPTHS REQUIRED BY CODE OF PRACTICE, WORKS (MINOR ROADS) AND DMR (ARTERIAL ROADS).



- Bollards shall be installed where padmounts are installed in car parks or other areas where padmounts are likely to be impacted by vehicles. The following outlines the minimum requirement for the design / installation of bollards: -

- Shall be manufactured of 5.6mm thick gal steel (medium)
- Circular tube min 140mm OD filled with concrete and capped.
- Buried 720mm in 400 x 400 x 720(D) concrete pad
- Installed 900mm above ground at 1.5m centers.

1. All materials and construction shall be in accordance with Australian Standards.
2. All concrete shall be minimum grade $F'c=25\text{MPa}$.
3. Galvanised pipe bollards may be painted to match the trim of surrounding dwellings.
4. A bollard will not be required provided a barrier such as a block wall, armo barrier or other permanent structure protects the PMT from vehicle traffic and likely impacts.

ENERGEX will not commission the transformer until the transformer site has been completed to ENERGEX specifications (including the concrete surround).

ENERGEX specifications for construction of the transformer site and installation of conduits on private property are available at the following web address.

https://swp.energex.com.au/service_providers/technical_docs/asp/technical_documents.asp

Section C1 - Conduits
Section C2 - Excavations & Reinstatements
Section C3 - Padmount Transformer Sites

Section 14 - Drawing 11040-A4-14-33 Sht 2

The site contractor is to refer all substation construction queries to their electrical consultant.

Cable conduit shall be of the following type;
125mm Dia UPVC Light Duty Rigid Pressure pipe to AS/NZS2053. Conduit bends shall have a Minimum radius of 1830mm.

The conduits shall be laid in a straight line with sealed joints. Should any deviation be required in conduit route, 1830mm radius bends shall be used. Bends shall not be greater than 30 degrees. Cable pits shall be used for greater deviations. Refer to ENERGEX Planner for details.


The conduits shall have 750mm minimum cover and shall be bedded on compacted sand or fine granular soil free of rocks. The socket ends of conduits shall finish 150mm beyond the R.P. alignment and shall have 750mm cover below finished fourth level. The R.P. alignment shall be marked by a bellmouth shall be provided where the conduits terminate in the substation wall or wall of a substation trench. A 2.5mm plastic coated steel draw wire or 6mm braided Polypropylene Rope "BORAL KA10850" shall be installed in each conduit (1kN min. breaking strength).

Because of the physical distortion likely in large groups of buried UPVC conduits, High Density conduits shall be used for groups of more than 6 conduits. Conduits shall be 125mm or 150mm as specified by ENERGEX and shall be supplied and installed by the developer. Conduits shall be securely sealed by builder to prevent ingress of dirt until cable installation by ENERGEX and then resealed by ENERGEX.

ENERGEX may need to install an earth wire and earth rods in conduit trenches from the substation site.

Electricity Supply Conduits and Cables shall have polymeric cable protection covers placed 100mm above the top conduit face of the electricity supply conduits and cables. Cable protection covers shall be lapped when placed together; 100mm minimum along the longitudinal axis, 40mm minimum along the traverse axis and shall extend 40mm minimum past the external edges of the conduit/cable bank.

Polymeric cable protection cover shall be a minimum of 5mm thick as described in Australian Standard; AS/NZS 4702 for Polymeric Cable Protection Covers.



- NOTE
1. INSTALL A NEW COMMUNICATIONS CONDUIT OF MINIMUM SIZE, 100mm LD PVC WHITE CONDUIT,

TYPICAL TRENCH CROSS SECTION FOR ENERGEX CONDUITS IN PRIVATE PROPERTY

TRADING AS:
ELECTRICAL DESIGN GROUP

USE FIGURED DIMENSIONS
IN PREFERENCE TO SCALE

ALL DIMENSIONS TO BE
VERIFIED ONSITE.

CULVERT INSPECTION REQUIRED BEFORE TRANSFORMER IS DELIVERED
- 48 HOURS PRIOR NOTICE NEEDED.
CONTACT on

TRANSFORMER WILL NOT BE ENERGISED UNTIL ALL REQUIREMENTS ARE MET.

ELECTRICAL DESIGN GROUP
ELECTRICAL BUILDING SERVICES CONSULTANTS
BRISBANE GOLD COAST

P.O.Box 15, Sherwood Q.4075
Phone: (07) 3278 4375
Email: brisbane@edg.net.au
Web: www.edg.net.au

PROJECT:
KINGS CHRISTIAN COLLEGE
WALLOON STAGE 1 PROJECT 2 WAL01

KARRABIN ROSEWOOD ROAD, WALLOON

REV.	DESCRIPTION:	DATE:
DRAWING:		

ELECTRICAL SERVICES

ENERGEX PADMOUNT SUBSTATION

STANDARD DETAILS

SCALE: NOT TO SCALE AT A1	PROJECT NO: C3808a	DRAWING NO: EN04	REVISION: A
------------------------------	------------------------------	----------------------------	-----------------------